

10/24/2008 3:41:26 PM
\\USORCA1P006\PROJECTS\Caltrans\IETM\500 CAD\Issued\2008-09-26_Bid Addendum #201-Drawings\BIM\IETM\BLOC-independent.rvt

F

D


C

B


A

1. CHARACTER TYPE: CHARACTERS ON SIGNS SHALL BE RAISED 1/32 INCH (0.794mm) MINIMUM AND SHALL BE SANS SERIF UPPERCASE CHARACTERS ACCOMPANIED BY GRADE 2 BRAILLE (SEE NOTE 9 BELOW).
2. CHARACTER SIZE: RAISED CHARACTERS SHALL BE A MINIMUM OF 5/8 INCH (15.9mm) AND A MAXIMUM OF 2 INCHES (51mm) HIGH.
3. FINISH AND CONTRAST: CONTRAST BETWEEN CHARACTERS, SYMBOLS AND THEIR BACKGROUND MUST BE 70% MINIMUM AND HAVE A NON-GLARE FINISH. (1117B.5.2)
4. PROPORTIONS: CHARACTERS ON SIGNS SHALL HAVE A WIDTH-TO-HEIGHT RATIO OF BETWEEN 3:5 AND 1:1 AND A STROKE WIDTH-TO-HEIGHT RATIO OF BETWEEN 1:5 AND 1:10. (1117B.5.3)
- ALL LETTERS MEASURED MUST BE UPPERCASE. AFTER CHOOSING A TYPESTYLE TO TEST, BEGIN BY PRINTING THE LETTERS I, X, AND O AT 1 INCH HIGH. PLACE THE TEMPLATES 3:1 SQUARE OVER THE X OR O, WHICHEVER IS NARROWER. IF THE CHARACTER IS NOT WIDER THAN 1 INCH, NOR NARROWER THAN THE 3:5 RECTANGLE, THE PROPORTIONS ARE CORRECT. USE THE 1:5 RECTANGLE TO DETERMINE IF THE STROKE OF THE I IS TOO BROAD, AND THE 1:10 RECTANGLE TO SEE IF IT IS TOO NARROW. IF ALL THE TESTS ARE PASSED, THE TYPESTYLE IS COMPLIANT WITH PROPORTION CODE.

TEMPLATE FOR CHECKING CHARACTER AND STROKE WIDTH TO HEIGHT PROPORTIONS:



5. BRAILLE: CONTRACTED CALIFORNIA GRADE 2 BRAILLE SHALL BE USED WHEREVER BRAILLE IS REQUIRED IN OTHER PORTIONS OF THESE STANDARDS. DOTS SHALL BE 1/10 INCH (2.54 mm) ON CENTERS IN EACH CELL WITH 2/10 INCH (5.08mm) SPACE BETWEEN CELLS, MEASURED FROM THE SECOND COLUMN OF DOTS IN THE FIRST CELL TO THE FIRST COLUMN OF DOTS IN THE SECOND CELL. DOTS SHALL BE RAISED A MINIMUM OF 1/40 INCH (0.635mm) ABOVE THE BACKGROUND. (1117B.5.6)



RECOMMEND ROUNDED OR DOMED CALIFORNIA BRAILLE DOTS, EACH DISTINCT AND SEPARATE. DOTS WITH STRAIGHT SIDES AND FLAT TOPS ARE NOT READABLE FOR MANY BRAILLE USERS.

1 | SIGNAGE NOTES

A-754

NOT TO SCALE

INTERIOR SIGNAGE SCHEDULE				
Mark	Detail	Quantity	Sign Text	Sign Remarks
1	25/A-755	3		EVACUATION PLAN
3	15D/A-755	1	ELEVATOR MACHINE ROOM 102	
5	28/A-755	2	ASSISTIVE LISTENING DEVICE AVAILABLE	
6	7A/A-755	5		RESTROOM DOOR SIGN
7	7B/A-755	5		RESTROOM WALL SIGN
8	12/A-755	5		STAIR LEVEL IDENTIFICATION SIGN
9	15D/A-755	1	FACILITY MANAGER, STATIONARY ENGINEER, MAINTENANCE MECHANIC 104	
10	15D/A-755	1	IT SUPPORT 105	
11	15D/A-755	1	CALTRANS TELEPHONE ROOM 106	
12	15D/A-755	1	COMPUTER EQUIPMENT ROOM 132A	
13	15D/A-755	1	CALTRANS STORAGE ROOM 113A	
14	15D/A-755	1	SUPPLY GROUP LAB & FILE 113B	
15	15D/A-755	1	IDF ROOM 114	
16	15D/A-755	1	DGS RADIO VAULT 116	
17	15D/A-755	1	JANITOR 117	
18	15D/A-755	1	OFFICE MACHINE ROOM & STORAGE 118	
19	15D/A-755	2	WOMENS LOCKERS	
20	15D/A-755	2	MENS LOCKERS	
21	15D/A-755	1	SHIPPING & RECEIVING 122	
22	15D/A-755	1	ELECTRICAL ROOM 123	
23	15D/A-755	1	UPS BATTERY ROOM 129	
24	15D/A-755	1	CHP STORAGE ROOM 130	
25	15D/A-755	2	COMMUNICATION ROOM 131	
26	15D/A-755	1	SERGEANTS 134	NAME TAG INSERT OPTION
27	15D/A-755	1	COMM ICC CAPTAIN 135	NAME TAG INSERT OPTION
28	15D/A-755	1	EXECUTIVE LIEUTENANT 136	NAME TAG INSERT OPTION
29	15D/A-755	2	BRIEFING & TRAINING ROOM 138	
30	15D/A-755	1	CHP NETWORK SERVER ROOM 133	
31	15D/A-755	1	CHP TELEPHONE ROOM 139	
32	15D/A-755	1	PUBLIC INFORMATION OFFICER 202	NAME TAG INSERT OPTION
33	15D/A-755	1	CONFERENCE ROOM 203	
34	15D/A-755	1	PRESS & VISITOR ROOM 204	
35	15D/A-755	1	HALLWAY 242	
36	15D/A-755	4	CONTROL ROOM 230	
37	15D/A-755	2	EMERGENCY RESPONSE CENTER 205	
38	15D/A-755	2	EMERGENCY OPERATIONS CENTER 206	
39	15D/A-755	1	JANITOR 209	
40	15D/A-755	1	IDF ROOM 210	
41	15D/A-755	1	CHP STORAGE ROOM 211	
42	15D/A-755	1	KITCHEN & BREAK ROOM 213	
43	15D/A-755	1	STORAGE & SUPPLY ROOM 216	
44	15D/A-755	1	LACTATION ROOM 217	
45	15D/A-755	1	TMC MANAGER 219	
46	15D/A-755	1	MAINTENANCE COMM SUPERINTENDENT 220	NAME TAG INSERT OPTION
47	15D/A-755	1	AMATEUR RADIO ROOM 221	
48	15D/A-755	1	PLOTTER, COPY & MAIL 222	
49	15D/A-755	1	OFFICE MACHINE ROOM 223	
50	15D/A-755	1	SECURITY VAULT 224	
51	15D/A-755	1	ELECTRICAL ROOM 225	
52	15D/A-755	1	TM OFFICE CHIEF 226	NAME TAG INSERT OPTION
53	15D/A-755	1	TMT LEADER 227	NAME TAG INSERT OPTION
54	15D/A-755	1	TMC LEADER 228	NAME TAG INSERT OPTION
55	15D/A-755	1	DISPATCH SUPERVISOR 229	NAME TAG INSERT OPTION
56	15D/A-755	2	PROJECTION ROOM 232	
57	15D/A-755	1	CAD COORDINATOR & EQUIPMENT 233	NAME TAG INSERT OPTION
58	15D/A-755	3	PSDS 1 234	
59	15D/A-755	1	PSDS 2 235	
60	15D/A-755	1	INTERVIEW 236	
61	15D/A-755	1	PLAYBACK & TAPE STORAGE 237	
62	15D/A-755	1	CHP IDF ROOM 238	
63	15D/A-755	1	BOILER ROOM 302	
64	15A/A-755	5	EXIT	
65	15B/A-755	22	EXIT ROUTE	
66	15C/A-755	3	EXIT STAIR DOWN	
70	14/A-755	2		INT'L SYMBOL OF ACCESSIBILITY
71	15D/A-755	1	SNACK BAR 115	
72	15D/A-755	1	SNACK BAR 231	
73	11A/A-755	1		STAIRWELL ID SIGN- FIRST FLOOR
74	11A/A-755	1		STAIRWELL ID SIGN- SECOND FLOOR
75	11A/A-755	1		STAIRWELL ID SIGN- ROOF
76	15D/A-755	1	HALLWAY 142	
77	15D/A-755	1	COMPUTER EQUIPMENT ROOM 132B	
78	27/A-755	1	AIR CLEANER	
79	13/A-755	1	MAXIMUM CAPACITY IN THIS ROOM: 54 OCCUPANTS	OCCUPANT LOAD SIGN
80	13/A-755	5	MAXIMUM LIVE LOAD 125 PSF AROUND EQUIPMENT	
81	13/A-755	3	MAXIMUM LIVE LOAD 125 PSF	MAXIMUM LIVE LOAD SIGN
82	13/A-755	1	MAXIMUM LIVE LOAD 250 PSF	MAXIMUM LIVE LOAD SIGN
83	13/A-755	3	MAXIMUM LIVE LOAD 300 PSF	MAXIMUM LIVE LOAD SIGN
84	13/A-755	2	MAXIMUM CAPACITY IN THIS ROOM: 49 OCCUPANTS	OCCUPANT LOAD SIGN
85	12A/A-755	1		STAIR LEVEL ID SIGN- FIRST FLOOR
86	12B/A-755	1		STAIR LEVEL ID SIGN- SECOND FLOOR
87	12C/A-755	1		STAIR LEVEL ID SIGN- ROOF
88	13/A-755	1	ANY TEMPORARY SUPPORT OR JACKING OF COLUMNS MUST UTILIZE TWO JACK POINTS MINIMUM AT EACH COLUMN AT ALL TIMES	
89	13/A-755	31	ANY TEMPORARY SUPPORT OR JACKING OF COLUMNS MUST UTILIZE TWO JACK POINTS MINIMUM AT EACH COLUMN AT ALL TIMES	LOCATE SIGN AT EACH BASE ISOLATOR, SEE DETAIL 4/A-200

INTERIOR SIGNAGE LEGEND

1 SIGN MARK

△ SIGN

PROJECT



PROJECT ADDRESS
1392 VICTORIA STREET
FONTANA, CA 92336

CLIENT



STATE OF CALIFORNIA
DEPARTMENT OF GENERAL SERVICES
REAL ESTATE SERVICES DIVISION
PROJECT MANAGEMENT BRANCH
707 THIRD STREET, SUITE 3-305
WEST SACRAMENTO, CA 95605
PROJECT DIRECTOR: RAPAT ALAFRANJI
TELEPHONE: (916) 376-1728

DESIGNER

DMJM H&N | AECOM

899 TOWN & COUNTRY ROAD, ORANGE, CALIFORNIA 92668
T: 714-967-2400 F: 714-967-2729 www.dmjmn.com

CONSULTANT

DSA STAMP

IDENTIFICATION STAMP
DIVISION OF THE STATE ARCHITECT
OFFICE OF REGULATION SERVICE

APPL. #: 04-109200-2
AC _____ FLS _____ SS _____
DATE _____

FILE NUMBER: RESD

STATUS

JULY 30, 2008

ISSUE


C	10/27/08	BID PERIOD ADDENDUM #5
MARK	DATE	DESCRIPTION

PROJECT NO: 60004333.4000

DRAWN BY: GJ

CHECK BY: JR

STAMP



SHEET TITLE

INTERIOR/EXTERIOR
SIGNAGE SCHEDULE

A-754