

10/28/2008 11:06:20 AM  
C:\Projects\Caltrans\ETM\CM\TMC\_BLDG-Gretchen.rvt

FINISH SCHEDULE										
NUMBER	NAME	FLOOR FINISH	BASE FINISH	NORTH WALL FINISH	EAST WALL FINISH	SOUTH WALL FINISH	WEST WALL FINISH	CEILING FINISH	CEILING HEIGHT	COMMENTS
101	LOBBY	TER-1	TER-1	P-1 & P-3	P-1 & P-3	P-1	WV-1	P-1	13'-0"	
102	ELEVATOR MACHINE ROOM	SEA-1	B-3	P-1	P-1	P-1	P-1	ES	17'-0"	
103A	VISITOR RESTROOM	CTF-1	CTW-1	CTW-1	CTW-1	CTW-1	CTW-1	GYP-1	8'-0"	
103B	RESTROOM VESTIBULE	TER-1	TER-1	P-1	P-1	P-1	P-1	GYP-1	8'-0"	
104	FAC. MGR, STA. ENGINEER, MAINT. MECH.	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	
105	IT SUPPORT	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	
106	CALTRANS TELEPHONE RM	VCT-3	B-2	P-1	P-1	P-1	P-1	ES	17'-0"	
107	TMS SPECIALIST	CPT-1/CPT-2	B-1	-	P-1	P-1	P-1	ACT-2	9'-6"	
108	TMS STAFF	CPT-1/CPT-2	B-1	-	P-1	P-1	P-1	ACT-2	9'-6"	
109	TMS OFFICE CHIEF	CPT-1/CPT-2	B-1	-	P-1	P-1	P-1	ACT-2	9'-6"	
110	TMS MTCE CONTRACTOR	CPT-1/CPT-2	B-1	-	P-1	P-1	P-1	ACT-2	9'-6"	
111	AUX. FUNCTION / RADIO TECH.	CPT-1/CPT-2	B-1	-	P-1	P-1	P-1	ACT-2	9'-6"	
112	RAMP METERS	CPT-1/CPT-2	B-1	-	P-1	P-1	P-1	ACT-2	9'-6"	
113A	CALTRANS STORAGE RM	*VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	*VCT RANDOM MIX
113B	SUPPLY GROUP LAB FILE	*VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	*VCT RANDOM MIX
114	IDF RM 1	*VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	ES	17'-0"	*VCT RANDOM MIX
115	SNACK BAR 1	*VCT-1 & VCT-2	B-1	P-2	P-2	P-2	P-2	ACT-2	8'-6"	*VCT RANDOM MIX
116	DGS RADIO VAULT	EPX-1	B-1	P-1	P-1	P-1	P-1	ES	17'-0"	
117	JANITOR	VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	GYP-1	9'-0"	
118A	OFFICE MACHINE RM 1	VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	ACT-2 & GYP-1	9'-0"	
118B	STORAGE / SUPPLY RM 1	VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	
119A	CHP WOMENS RESTROOM	CTF-1	CTW-1	CTW-1	P-1	CTW-1 & P-1	CTW-1	GYP-1	9'-0"	
119B	CHP WOMENS LOCKERS	CTF-1	CTW-1	CTW-1 & P-1	P-1	CTW-1 & P-1	CTW-1	GYP-1	9'-0"	
120A	CHP MENS RESTROOM	CTF-1	CTW-1	CTW-1 & P-1	P-1	CTW-1	CTW-1	GYP-1	9'-0"	
120B	CHP MENS LOCKERS	CTF-1	CTW-1	CTW-1 & P-1	P-1	CTW-1 & P-1	CTW-1	GYP-1	9'-0"	
121	FIRE RISER RM	EPX-1	B-3	P-1	P-1	P-1	P-1	ES	17'-0"	
122	SHIPPING / RECEIVING	EPX-1	B-3	P-1	P-1	P-1	P-1	ES	17'-0"	
123	ELECTRICAL RM	EPX-1	B-3	P-1	P-1	P-1	P-1	ES	17'-0"	
124	ELEC. OPS SPV.	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-6"	
125	ELEC. OPS / TRAFFIC SIGNAL STAFF	CPT-1	B-1	P-1	P-1	-	P-1	ACT-2	9'-6"	
126	TRAFFIC SIGNAL STAFF	CPT-1	B-1	P-1	P-1	-	P-1	ACT-2	9'-6"	
127	TMC OFFICERS	CPT-1	B-1	P-1	P-1	-	P-1	ACT-2	9'-6"	
128	TRAFFIC OFFICERS / FSP	CPT-1	B-1	P-1	P-1	-	P-1	ACT-2	9'-6"	
129	UPS BATTERY RM	EPX-1	B-3	P-1	P-1	P-1	P-1	ES	17'-0"	
130	CHP STORAGE RM 1	*VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	*VCT RANDOM MIX
131	COMMUNICATION RM	VCT-3	B-2	P-1	P-1	P-1	P-1	ES	17'-0"	
132A	COMPUTER EQUIPMENT RM 2	VCT-3	B-2	P-1	P-1	P-1	P-1	ES	17'-0"	
132B	COMPUTER EQUIPMENT RM 1	VCT-3	B-2	P-1	P-1	P-1	P-1	ES	17'-0"	
133	CHP CAD / NETWORK SERVER RM	VCT-3	B-2	P-1	P-1	P-1	P-1	ES	17'-0"	
133A	FM200 TANK CLOSET	VCT-3	B-2	P-1	P-1	P-1	P-1	ES	17'-0"	
134	SERGEANTS	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	
135	COMM. ICC CAPT.	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	
136	EXEC. LIEUTENANT	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	
137	CLERICAL	CPT-1	B-1	P-2	P-2	P-2	-	GYP-1	10'-0"	
138	BRIEFING / TRAINING RM	CPT-1	B-1	P-1	P-1	P-1	P-1 & P-3	ACT-2	10'-0"	
139	CHP TELEPHONE RM / MPOE	VCT-3	B-2	P-1	P-1	P-1	P-1	ES	17'-0"	
140	HALLWAY	CPT-2	B-2	P-3	-	-	P-1	ACT-1	8'-6"	
141	HALLWAY	CPT-2	B-2	-	P-1	*P-1 & P-3	P-1 & P-3	ACT-1	8'-6"	*NOTE 2
142	HALLWAY	CPT-2	B-2	P-1	-	P-3	P-1	ACT-1, GYP-1	8'-6"	
143	CORRIDOR	CPT-2	B-2	P-1	P-1	P-1	P-1 & P-3	ACT-1	9'-0"	
S01	STAIR 1	*TER-1/TER-2	-	P-1	P-1	P-3	-	GYP-1	27'-0"	*TER-2 ON TREADS ONLY
S02	STAIR 2	*RTF-1/RTF-2	B-2	P-2	P-2	P-2	P-2	GYP-1	43'-1 1/4"	*RTF-1 ON TREADS/RISERS
201	CORRIDOR	TER-1	TER-1	P-3	P-1 & P-3	P-1	P-1	ACT-1	10'-0"	
202	PUBLIC INFO OFFICER	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	
203	CONFERENCE RM	CPT-1	B-1	P-1 & P-2	P-1	P-1	P-1	GYP-1	10'-0"	
204	PRESS / VISITOR	CPT-1	B-1	P-3	P-1	P-1	P-1	ACT-2	10'-0"	
205	EMERGENCY RESPONSE CENTER	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	12'-0"	
205A	ERC STOR	CPT-1	B-1	P-1	P-1	P-1	P-1	ES	10'-0"	
206	EMERGENCY OPERATIONS CENTER	CPT-1	B-1	P-1	P-1	P-1	P-1	ES	12'-0"	
206A	EOC STOR	CPT-1	B-1	P-1	P-1	P-1	P-1	ES	10'-0"	
207	DTM OFFICE CHIEF	CPT-1	B-1	-	P-1	P-1	P-1	ACT-2	10'-0"	
208	DTM STAFF	CPT-1	B-1	-	P-1	P-1	P-1	ACT-2	10'-0"	
209	JANITOR / VACUUM	*VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	GYP-1	9'-0"	*VCT RANDOM MIX
210	IDF 2	*VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	ES	17'-0"	*VCT RANDOM MIX
211	CHP STORAGE 2	*VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	*VCT RANDOM MIX
212	DTM STAFF	CPT-1	B-1	P-3	P-3	-	-	ACT-1	9'-0"	
212A	VALVE CLOSET	EPX-1	B-3	P-1	P-1	P-1	P-1	ES	8'-0"	
213	KITCHEN / BREAK	*VCT-1, VCT-2 & CPT-1	B-1 & B-3	P-3	P-1	P-1	P-1	ACT-2 & GYP-1	10'-0"	*VCT RANDOM MIX
214A	CALTRANS WOMENS RESTROOM	CTF-1	CTW-1	CTW-1 & P-1	P-1	CTW-1 & P-1	CTW-1	GYP-1	9'-0"	
214B	CALTRANS WOMENS LOCKERS	CTF-1	CTW-1	CTW-1 & P-1	P-1	CTW-1 & P-1	CTW-1	GYP-1	9'-0"	
215A	CALTRANS MENS RESTROOM	CTF-1	CTW-1	CTW-1 & P-1	P-1	CTW-1 & P-1	CTW-1	GYP-1	9'-0"	
215B	CALTRANS MENS LOCKERS	CTF-1	CTW-1	CTW-1 & P-1	P-1	CTW-1 & P-1	CTW-1	GYP-1	9'-0"	
216	STORAGE / SUPPLY 2	*VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	*VCT RANDOM MIX
217	LACTATION RM	CPT-1	B-1	P-2	P-2	P-2	P-2	ACT-2	9'-0"	
218	CLERICAL	CPT-1	B-1	P-2	P-2	P-1	P-2	GYP-1	10'-0"	
219	TMC MANAGER	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	
220	MAINT. COMM. SUPERINTENDENT	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	
221	AMATEUR RADIO	*VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	*VCT RANDOM MIX
222	PLOTTER / COPY / MAIL / SUPPLY	*VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	*VCT RANDOM MIX
223	OFFICE MACHINE RM 2	*VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	*VCT RANDOM MIX
224	SECURITY VAULT	*VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	*VCT RANDOM MIX
225	ELECTRICAL RM 2	EPX-1	B-3	P-1	P-1	P-1	P-1	ES	17'-0"	
226	TM OFFICE CHIEF	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	
227	TMT LEADER	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	
228	TMC LEADER	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	
229	DISPATCH SUPERVISOR	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	
230	CONTROL RM	CPT-3	B-1	P-3	P-1/AWP-1	P-1/AWP-1	P-1/AWP-1	ACT-1, GYP-1	23'-0"	
231	SNACK BAR 2	VCT-3	B-1	P-1	P-3	P-1	P-1	ACT-2	7'-9"	
232	PROJECTION RM	VCT-3	B-1	P-5	P-5	P-5	P-5	ES	18'-8"	
232A	MECH. RM A	EPX-1	B-3	P-1	P-1	P-1	P-1	ES	16'-5"	
232B	MECH. RM B	EPX-1	B-3	P-1	P-1	P-1	P-1	ES	16'-5"	
233	CAD COORDINATOR / EQUIPMENT	VCT-3	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	
234	PSDS 1	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	10'-0"	
235	PSDS 2	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	
236	INTERVIEW	CPT-1	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	
237	PLAYBACK / TAPE STORAGE	*VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	ACT-2	9'-0"	*VCT RANDOM MIX
238	CHP IDF 3	*VCT-1 & VCT-2	B-1	P-1	P-1	P-1	P-1	ES	17'-0"	*VCT RANDOM MIX
240	HALLWAY	CPT-2	B-2	P-1	P-1	P-3 & P-1	-	ACT-1	9'-0"	
241	HALLWAY	CPT-2	B-2	P-1	P-1	-	*P-1 & P-3	ACT-1	9'-0"	*P-3 AT RESTROOM ALCOVE
242	HALLWAY	CPT-2	B-2	P-1	P-1	P-1	P-1	ACT-1	9'-0"	*NOTE 3
301	MECHANICAL ROOM									
302	BOILER ROOM	EPX-1	B-3	P-1	P-1	P-1	P-1	ES	8'-0"	
303	ELEVATOR LANDING	EPX-1	B-3	P-1	P-1	P-1	P-1	GYP-1	12'-6"	

NOTE:  
1. SEE FLOOR FINISH PLANS FOR LOCATION OF DIFFERENT PAINT COLORS ON THE SAME WALL.  
2. SEE DETAIL 114A-622 FOR PAINT COLOR AT RESTROOM ALCOVES.  
3. SEE DETAIL 254A-622 FOR PAINT COLOR AT EVC ALCOVE.

## INTERIOR FINISH AND COLOR LEGEND

### ACOUSTICAL WALL PANEL (AWP)

AWP-1 MFR: ACOUSTICAL SOLUTIONS, INC. ALPHASORB SIZE: 2'x8' COLOR: AS SELECTED FROM MFR FULL RANGE 2" THICK, BEVELED EDGE, CLASS A FACED W/ FIBERGLASS FABRIC BY GILFORD OF MAIN

### ACOUSTICAL CEILING TILE (ACT)

ACT-1 MFR: ARMSTRONG OPTIMA VECTOR PLANK #3907, WHITE (24"X96"X7/8"), SUSPENSION SYSTEM: PRELUDE XL15/16" EXPOSED TEE LOCATION: HALLWAYS, ACOUSTICAL WALL PANELS

ACT-2 MFR: ARMSTRONG OPTIMA VECTOR #3900, WHITE (24"X24"X7/8"), SUSPENSION SYSTEM: PRELUDE XL15/16" EXPOSED TEE LOCATION: GENERAL

### WALL BASE (B)

B-1 MFR:ALLSTATE STYLE: TS RUBBER VULCANIZED THERMOSET SOLID WALL BASE COLOR: #12 LOCATION: AT CPT-1 & 3, VCT-1 & 2

B-2 MFR:ALLSTATE STYLE: TS RUBBER VULCANIZED THERMOSET SOLID WALL BASE COLOR: #03 LOCATION: AT CPT-2, VCT-3

B-3 MFR:ALLSTATE STYLE: TS RUBBER VULCANIZED THERMOSET SOLID WALL BASE COLOR: #04 LOCATION: AT EPX-1, SEA-1

### CARPET (CPT)

CPT-1 MFR:INTERFACE STYLE: # 12501 STONEPATH TILE COLOR: # 6580 TRAVERTINE LOCATION: GENERAL

CPT-2 MFR:INTERFACE STYLE: # 16182 TATAMI TILE COLOR: # 1842 KOBE LOCATION: HALLWAYS

CPT-3 MFR: JULIE INDUSTRIESSTYLE: STATIC SMART ESD, FRONTIER SERIES LOCATION: CONTROL ROOM COLOR: 4125 BOONE

### CERAMIC TILE (CTF-FLOOR CTW-WALL)

CTW-1 MFR:INNOVATIVE CERAMICS COLOR: R-110 SIZE: 4"X8" (VISION RECYCLED TILE) PATTERN: RUNNING BOND LOCATION: RESTROOMS

CTF-1 MFR:INNOVATIVE CERAMICS COLOR: R-210 SIZE: 4"X8" (VISION RECYCLED TILE) PATTERN: RUNNING BOND LOCATION: RESTROOMS

### EXPOSED CONC. FLOOR- EPOXY COATING (EPX)

EPX-1 MFR: TNEMEC SERIES 280 TNEME-GLAZE COLOR: AS SELECTED FROM FULL RANGE

### EXPOSED CONC. FLOOR- SEALER (SEA)

SEA-1

### GYPSON BOARD CEILING (GYP-1)

GYP-1 GWB CEILING COLOR: P-1

### PAINT COLOR (P)

P-1 MFR: DUNN-EDWARDS COLOR#: DEW340, WHISPER

P-2 MFR: DUNN-EDWARDS COLOR#: DE5287, ALLURING LIGHT

P-3 MFR: DUNN-EDWARDS COLOR#: DE5525, PALE VIEW

P-4 MFR: SCUFFMASTER STYLE: SOLID METAL, COLOR#: SM887

P-5 MFR: DUNN-EDWARDS COLOR#: DEA187 BLACK LOCATION: PROJECTION ROOM

### PERFORATED STAINLESS STEEL PANEL (PSP)

PSP-1 MFR: ACCURATE METAL FABRICATING PERFORATION: SQUARE STRAIGHT, 16% OPEN, 0.2" SQ. x 1/2" CTRS INSTALL PER SPEC SECTION 057300 COLOR: STAINLESS STEEL #4 FINISH LOCATION: STAIR GUARDRAIL PANELS

### PLASTIC LAMINATES (PLM)

PLM-1 MFR:WILSONART COLOR & PATTERN: # 4637-60 MONTEREY HAZE LOCATION: MILLWORK CABINET FRONTS, RR PANELS

PLM-2 MFR: WILSONART COLOR & PATTERN: # 4639-60 MONTEREY STORM LOCATION: MILLWORK CABINET TOPS, BREAK ROOM/SNACK BAR CABINET FRONTS

### RUBBER TILE FLOORING (RTF)

RTF-1 MFR: JOHNSONITE STYLE: BAMBOO TREAD/RISER (VIBMTR) COLOR: 190 GREEGE

RTF-2 MFR: JOHNSONITE STYLE: BAMBOO RUBBER TILE (BMRT) COLOR: 190 GREEGE

### STAINLESS STEEL GRATING (SSG)

SSG-1 MFR: KADEE STYLE: KD58, SS CLEAN TREAD LOCATION: ENTRY DOORS

### SOLID SURFACE (SSU)

SSU-1 MFR: SAMSUNG STARON STYLE & COLOR: # PA860, PEBBLE AQUA LOCATION: RESTROOM COUNTERTOPS

SSU-2 MFR: CORIAN STYLE & COLOR : MOSS (C) LOCATION: KITCHEN COUNTERTOPS

### TERRAZZO (TER)

TER-1 MFR: CORRADINI SAMPLE #: 6392-1-E, MIN THICKNESS 3/8" LOCATION: FIRST AND SECOND FLOOR LOBBY AND