SECTION 12490

WINDOW TREATMENT

PART 1 GENERAL

1.01 SUMMARY

A. Provide sliding panels window treatment systems with operating hardware, attachments, and accessories as required for complete finished operational installation.

1.02 SUBMITTALS

A. Product Data: Manufacturer's specification sheet.

B. Material Sample: Submit two samples of shade fabric.

1.03 DELIVERY, STORAGE AND HANDLING

A. Product to be delivered to jobsite in manufacturer's original packing.

B. Products to be handled and stored to prevent damage to materials, finishes and operating mechanisms. Store in a clean, dry area, laid flat to prevent sagging and twisting of packaging.

1.04 PROJECT / SITE CONDITIONS

A. Building shall be enclosed; and windows, frames and sills shall be installed and glazed.

B. Wet work shall be complete and dry.

C. Ceilings, window pockets, electrical and mechanical work above window covering shall be complete.

D. Electrical power (110 volt AC) shall be available for installer's tools within 500 feet of product installation areas.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Levelor Corp.

B. Bali Blinds

C. Hampton Bay

D. Substitutions: Refer to Section 01640 – Substitutions and Product Options.

2.02 MATERIALS

A, Sliding Panels: As detailed on drawings.
1. Shade Fabric: As noted on drawings.

2. Mounting: Outside mount with projection brackets at Building #3 bedrooms and inside mount at other areas as indicated on drawings.
3. Valance: Provide with returns and return brackets at outside mount condition.
4. Control: Wand.

PART 3 EXECUTION

3.01 INSTALLATION

A. Install sliding panels in accordance with blinds manufacturer's recommendations and installation instructions.
   1. Provide templates where necessary for preparation of sash for installation of blinds.

B. Secure in place with mechanical fasteners.

C. Adjust parts for smooth operation.

END OF SECTION