LIGHTING FIXTURE SCHEDULE

TYPE	DESCRIPTION	FINISH	LAMP(S)	REMARKS	MANUFACTURER & NO.
A 64	2'x4' FLUORESCENT RECESS MOUNTED, 120 VOLT	WHITE	(2)-32W T8	PROVIDE EMERGENCY PACK WHERE REQUIRED	LITHONIA LIGHTING #2SPG232 RN A12 120 GEB310
B 64	8.3"Wx2.75"Hx48" SURFACE MOUNTED FLUORESCENT, 120 VOLT	WHITE	(2)-32W T8	-	KENALL #RB-48-232 RB2-120 PSS
C 64	LINEAR FLOURESCENT SURFACE MOUNTED, 120 VOLT	WHITE	(2)-F32W T8	-	DAY-BRITE LIGHTING PHILIPS #VMP-2-32-WP 120 1/2 EB
D 5	12"W x 8 1/4"H x 2 1/4" D SURFACE/PENDANT MOUNTED EXIT SIGN 120 VOLT	WHITE HOUSING	FACTORY (5W)	MASTER AND REMOTE EXIT SIGN. VANDAL PROOF AND WITH WIREGUARD.	EVENLITE #RZMR-EM-R-1-WW-AN-W-PC1
D1 5	12"W x 8 1/4"H x 2 1/4"D WALL MOUNTED LED EXIT SIGN 120 VOLT	WHITE HOUSING	FACTORY (5W)	VANDAL PROOF AND WITH WIREGUARD.	EVENLITE #RZMR-EM-R-1-WW-AN(X)
E 18	6" DIA. APERTURE DOWNLIGHT PREMIUM GLASS LENS 120 VOLT	WHITE	(1)18W DTT	PROVIDE EMEGENCY BATTERY PACK, WHERE REQUIRED.	CAPRI LIGHTING #CF-RIC-62H18-Q-V-1 R6232
F 26	6" DIA. COMPACT FLOURESCENT DOWNLIGHT 120 VOLT.	WHITE	(1)26W TT (2)26W	-	LIGHTOLIER #6031CL/S6132BUADV
G 32	11"DIA. x 7 1/2" CEILING, SURFACE MOUNTED FLUORESCENT, 120V	WHITE	(1)-32W CTTC	PROVIDE EMERGENCY BATTERY PACK WHERE REQUIRED	FALL SAFE #CCTC-TC-PP-32 A 120V-EBP-VRSD
H 32	11"DIA. x 7 1/2" WALL, SURFACE MOUNTED FLUORESCENT, 120V	WHITE	(1)-32W CTTC	PROVIDE EMERGENCY BATTERY PACK WHERE REQUIRED	FALL SAFE #CCTC-TC-HE-32 A 120V-EBP-VRSD

SANTA ANA UNIFIED SCHOOL DISTRICT

gkkworks
2355 Main Street Suite 220
Irvine | CA 92614
949 250 1500
949 955 2708 fax

Architect Seal

LICENSED ARCHITECT
GUILLERMO AGUILAR
NO. C13165
REN.: MAY 2011
STATE OF CALIFORNIA

Consultant and Seal

TMAD TAYLOR &GAINES
- STRUCTURAL
- MECHANICAL
- ELECTRICAL
- CIVIL

800 North Ferrari Lane, Suite 100
Ontario, California 91764
Phone: 909.477.6915 Fax: 909.477.6916
Project No. 2008.125.00

REGISTERED PROFESSIONAL ENGINEER
NESTOR C. TONDOTO, JR.
Lic. E16934
Exp. 6-30-2011
ELECTRICAL
STATE OF CALIFORNIA

Agency Approval

IDENTIFICATION STAMP
DIV. OF THE STATE ARCHITECT
APPL. 04-110031
AC ___ FLS ___ SS RH
DATE NOV 2 4 2009

No.	Date	Revision/Issue
	12/08/08	DSA SUBMITTAL
	02/11/09	DSA SUBMITTAL
	5/11/09	DSA BACKCHECK
	12/15/2011	BID SET

Project Name

MUIR
FUNDAMENTAL
SCHOOL MODERNIZATION

1951 MABURY ST.
SANTA ANA, CA 92707

Checked By	Drawn By
RA	KA

Sheet Title

LIGHTING FIXTURE SCHEDULE

Sheet Number

E0.7

Project Number	Scale
10021-010-00	NONE

©2009 gkkworks, All Rights Reserved
NO PART OF THE CONTENTS OF THIS DOCUMENT MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS WITHOUT THE WRITTEN PERMISSION OF GKKWORKS.

N:\20.CAD\TTG_Projects\2008\2008-125-00\Mpe\E0-7.dwg 10/02/2009