FINISH SCHEDULE

NOTE: ALL INTERIOR FINISHES SHALL COMPLY WITH CBC CHAPTER 8, CFC SECTION 1103.3.3, TITLE 19 CCR.

BUILDING NO.	ROOM NO.	DESCRIPTION	FLOORS: ONE-HOUR SEPARATION	FLOORS: CARPET	FLOORS: CERAMIC TILE	FLOORS: SHEET VINYL	FLOORS: VINYL COMP. TILE (VCT)	FLOORS: SEALED CONCRETE	FLOORS: QUARRY TILE	BASES: 4" RUBBER	BASES: CERAMIC TILE	BASES: QUARRY TILE W/ 3/8" R	BASES: SHEET VINYL 4" COVE	WALLS: VINYL WALL COVERING	WALLS: CERAMIC TILE	WALLS: PAINTED GYPSUM BD.	WALLS: FRP	WALLS: WAIN-SCOT HEIGHT	CEILINGS: 2X4' SUSPENDED ACOUSTICAL T-BAR GRID CEILING	CEILINGS: 2X2" SUSPENDED ACOUSTICAL T-BAR GRID CEILING	CEILINGS: 1" X 12" WOOD SLAT CEILING TILE OVER GYPSUM BOARD	CEILINGS: PAINTED GYPSUM BD.	CEILINGS: 1x4 T&G WOOD	CEILINGS: ROUGH CEILING HEIGHT	REMARKS
BUILDING "K"	1	KITCHEN	●						●			●				S	●		●			S		9'-0"	
	2	DRY STORAGE	●						●			●					●		●					9'-0"	
	3	SERVING LINE					●			●				●					●					9'-0"	
	4	ELECTRICAL / DATA ROOM	●					●		●						S						S		VARIES	
	5	CUSTODIAN	●						●			●				S						S		8'-0"	
	6	OFFICE							●			●		●					●					8'-0"	
	7	ENTRY							●			●				S						S		9'-0"	
	8	UNISEX TOILET			●						●					S						S		9'-0"	

BUILDING NO.	ROOM NO.	DESCRIPTION	FLOORS: ONE-HOUR SEPARATION	FLOORS: CARPET	FLOORS: CERAMIC TILE	FLOORS: SHEET VINYL	FLOORS: VINYL COMP. TILE (VCT)	FLOORS: SEALED CONCRETE	BASES: 4" RUBBER	BASES: CERAMIC TILE	BASES: QUARRY TILE W/ 3/8" R	BASES: SHEET VINYL 4" COVE	WALLS: VINYL WALL COVERING	WALLS: CERAMIC TILE	WALLS: PAINTED GYPSUM BD.	WALLS: FRP	WALLS: WAIN-SCOT HEIGHT	CEILINGS: 2X4' SUSPENDED ACOUSTICAL T-BAR GRID CEILING	CEILINGS: 2X2" SUSPENDED ACOUSTICAL T-BAR GRID CEILING	CEILINGS: 1" X 12" WOOD SLAT CEILING TILE OVER GYPSUM BOARD	CEILINGS: PAINTED GYPSUM BD.	CEILINGS: T&G WOOD	CEILINGS: ROUGH CEILING HEIGHT	REMARKS
BUILDING "A"	1	RECEPTION					●		●				●		S			●			S		VARIES	
	2	CLERKS		●					●				●					●			S		VARIES	
	3	CLERKS		●					●				●					●			S		VARIES	
	4	OFFICE MANAGER		●					●				●					●			S		VARIES	
	5	PTA OFFICE		●					●				●					●					8'-0"	
	6	CONFERENCE		●					●				●					●					9'-0"	
	7	PRINCIPAL		●					●				●					●					9'-0"	
	8	OFFICE		●					●				●					●					9'-0"	
	9	CLINIC				●			●						S			●					9'-0"	
	10	UNISEX TOILET			●						●			●							S		8'-0"	
	11	VICE PRINCIPAL		●					●				●					●					9'-0"	
	12	WORKROOM					●		●				●					●					9'-0"	
	13	OFFICE / VAULT	●	●					●				●								S		9'-0"	
	14	WORKROOM		●					●				●					●					9'-0"	
	15	WOMEN'S TOILET			●						●			●							S		8'-0"	
	16	LOUNGE		●			●		●				●					●					9'-0"	
	17	MEN'S TOILET			●						●			●							S		8'-0"	
	18	OFFICE		●					●				●								S		8'-0"	
	19	HEAD END / DATA / MDF	●				●		●						S						S		VARIES	
	20	ELECTRICAL	●					●	●						S						S		VARIES	
	21	CUSTODIAN	●				●		●						S						S		8'-0"	
BUILDING "B"	1	LIBRARY / MEDIA CENTER		●					●				●		S				●	●	S		VARIES	
	2	CLASSROOM / COMPUTER LAB		●					●				●					●					9'-0"	
	3	R.S.P.		●					●				●					●					9'-0"	
	4	OFFICE		●					●				●					●					9'-0"	
	5	DATA ROOM	●				●		●						S						S		VARIES	
	6	ELECTRICAL	●					●	●						S						S		VARIES	
BUILDING "C"	1	MULTI-PURPOSE ROOM					●		●				●		S			●			S	●	VARIES	
	2	TABLE STORAGE	●				●		●						S			●					9'-0"	
	3	VESTIBULE	●				●		●				●							●			8'-0"	
	4	MEN'S TOILET			●						●			●							S		8'-0"	
	5	WOMEN'S TOILET			●						●			●							S		8'-0"	
	6	PLATFORM RAMP		●					●				●								S		10'-6"	
	7	STORAGE	●				●		●						S						S		9'-0"	
	8	PLATFORM		●					●				●					●			S		VARIES	
	9	STORAGE	●				●		●						S						S		10'-6"	
	10	HALLWAY		●					●				●								S		10'-6"	
BUILDING "D"	1	CLASSROOM		●		●			●				●					●					9'-0"	
	2	CLASSROOM		●		●			●				●					●					9'-0"	
	3	CLASSROOM		●		●			●				●					●					9'-0"	
	4	CLASSROOM		●		●			●				●					●					9'-0"	
	5	CLASSROOM		●		●			●				●					●					9'-0"	
	6	CLASSROOM		●		●			●				●					●					9'-0"	
	7	CLASSROOM		●		●			●				●					●					9'-0"	
	8	CLASSROOM		●		●			●				●					●					9'-0"	
	9	DATA ROOM	●			●			●						S						S		VARIES	
	10	ELECTRICAL	●				●		●						S						S		VARIES	
	11	STORAGE	●			●			●						S			●					9'-0"	
	12	BOY'S TOILET			●						●			●							S		9'-0"	
	13	GIRLS TOILET			●						●			●							S		9'-0"	
	14	R.S.P.		●					●				●					●					9'-0"	
BUILDING "E"	1	CLASSROOM		●		●			●				●					●					9'-0"	
	2	CLASSROOM		●		●			●				●					●					9'-0"	
	3	CLASSROOM		●		●			●				●					●					9'-0"	
	4	CLASSROOM		●		●			●				●					●					9'-0"	
	5	CLASSROOM		●		●			●				●					●					9'-0"	
	6	CLASSROOM		●		●			●				●					●					9'-0"	
	7	CLASSROOM		●		●			●				●					●					9'-0"	
	8	CLASSROOM		●		●			●				●					●					9'-0"	
	9	DATA ROOM	●			●			●						S						S		VARIES	
	10	ELECTRICAL	●				●		●						S						S		VARIES	
	11	STORAGE	●			●			●						S			●					9'-0"	
	12	BOY'S TOILET			●						●			●							S		9'-0"	
	13	GIRLS TOILET			●						●			●							S		9'-0"	
	14	R.S.P.		●					●				●					●					9'-0"	
BUILDING "F"	1	CLASSROOM		●		●			●				●					●					9'-0"	
	2	CLASSROOM		●		●			●				●					●					9'-0"	
	3	CLASSROOM		●		●			●				●					●					9'-0"	
	4	CLASSROOM		●		●			●				●					●					9'-0"	
	5	CLASSROOM		●		●			●				●					●					9'-0"	
	6	CLASSROOM		●		●			●				●					●					9'-0"	
	7	CLASSROOM		●		●			●				●					●					9'-0"	
	8	CLASSROOM		●		●			●				●					●					9'-0"	
	9	DATA ROOM	●			●			●						S						S		VARIES	
	10	ELECTRICAL	●				●		●						S						S		VARIES	
	11	CUSTODIAN	●			●			●						S						S		VARIES	
	12	BOY'S TOILET			●						●			●							S		9'-0"	
	13	GIRLS TOILET			●						●			●							S		9'-0"	
	14	STORAGE	●			●			●						S			●					9'-0"	
	15	UNISEX TOILET			●						●			●							S		9'-0"	
	16	UNISEX TOILET			●						●			●							S		9'-0"	

● = PAINT
■ = ENAMEL (GLOSS)
● = SEMI GLOSS ENAMEL
F = FLAT WALL PAINT

LICENSED ARCHITECT JAMES M. SIMMONS C19096 RENEWAL 12/31/ STATE OF CALIFORNIA

REVISIONS | DATE

P S W C GROUP
ARCHITECTS / PLANNERS
1897 BUSINESS CENTER DR., SUITE 3, SAN BERNARDINO, CA. 92408
909/890-2233 FAX. 909/890-2844

ROOSEVELT II
ELEMENTARY SCHOOL
SAN BERNARDINO CITY UNIFIED SCHOOL DISTRICT
1261 W. 16TH STREET, SAN BERNARDINO, CA.

FINISH SCHEDULE

JOB NO. PS20
DRAWN BY
DATE 6/7/2011

A-9.1

RE-BID #F09-02 ROOSEVELT II (HENRY) E.S. NEW CONSTRUCTION BID ISSUANCE SET 12/09/11